

ROOM FINISH SCHEDULE							
ROOM NO.	NAME	FLOOR MATERIAL	BASE MATERIAL	WALL MATERIAL	CEILING MATERIAL	HEIGHT	REMARKS
MAIN LEVEL							
100	WAITING	EP	6-RR	ETR	ETR	2	
100A	VESTIBULE	EP	6-RR	ETR	ETR		
101	OFFICE AREA	ETR	ETR	ETR	ETR	2	
102	CORRIDOR	EP/EX	6-RR	ETR	ETR	1-2	
103	DIRECTOR OFFICE	EP	6-RR	ETR	ETR		
104	LABORATORY	EP	6-RR	ETR	ETR		
105	STAFF REPORT ROOM	EP	6-RR	ETR	ETR		
106	FILE ROOM	ETR	6-RR	ETR	ETR	2	
107	MENS LOCKERS	EP	6-RR	ETR	ETR		
108	WOMENS LOCKERS	EP	6-RR	ETR	ETR		
109	JANITOR	EP	6-RR	ETR	ETR		
110	GENERAL STORAGE	ETR	6-RR	ETR	ETR		
111	BREAK ROOM	EP	6-RR	ETR	ETR		
111A	VESTIBULE	EP	6-RR	ETR	ETR		
112	STRAY KENNEL AREA	FES	6-ETS	ETR	ETR	6-8	
113	KENNEL ANNEX	FES	6-ETS	ETR	ETR	6-8	
113A	KENNEL BITE AREA	FES	6-ETS	ETR	ETR	6-8	
114	ADOPTION AREA	FES	6-ETS	ETR	ETR	4.6-6	
115	EVALUATION ROOM	FES	6-ETS	ETR	ETR	4.6-6	
116	BONDING ROOM	FES	6-ETS	ETR	ETR		4.6-PROVIDE 6-RR @ CABINETS
117	CAI ADOPTION	FES	6-ETS	ETR	ETR	4	
118	CAI HALLWAY #1	FES	6-ETS	ETR	ETR		
119	CAI ISOLATION ROOM	FES	6-ETS	ETR	ETR	3	
120	VESTIBULE	EP	6-RR	ETR	ETR		
121	MECHANICAL ROOM	EP	6-RR	ETR	ETR	3	
122	FOOD PREPARATION	EP	6-RR	ETR	ETR	8	
123	FOOD STORAGE	EP	6-RR	ETR	ETR		
124	CAI HALLWAY #2	FES	6-ETS	ETR	ETR	4.8	
125	CAI HALLWAY #3	FES	6-ETS	ETR	ETR	4.8	
126	CHECK-IN	EP	6-EP	ETR	ETR	5	
127	VETERINARIAN ROOM	FES	6-ETS	ETR	ETR	4.6	
128	REFRIGERATION ROOM	FES	6-ETS	ETR	ETR		
129	GARAGE	TMS	6-TMS	ETR	ETR	7-8	

ROOM FINISH SCHEDULE ABBREVIATIONS:

EP EPOXY PAINT
EFS EPOXY FASTCURE FLOORING SYSTEM
TMS TROWEL WORKMAN SYSTEM
RR RUBBER BASE
EX EXISTING TO REMAIN

ROOM FINISH SCHEDULE REMARKS:

1. PROVIDE NEW RUBBER BASE AT NEW EP AREAS ONLY
2. PROVIDE NEW REDUCER STRIP BETWEEN EXISTING CARPET AND NEW EP OR DRINK CONDENSERS SECTION TO RESPECT FLOOR TO DRAINAGE FLOOR
3. PAINT BASED UNDERCOATING PAQ AREAS INCLUDING FACE OF PAQ.
4. REMOVE AND RENSAIL EXISTING CASIS AND TRENCH FLOOR DRAM COVERS AS REQUIRED TO INSTALL FLOORING SYSTEM
5. BUT EXISTING CASIS IN CONCRETE FLOOR
6. RESAL EXISTING CASIS IN CONCRETE FLOOR

FLOOR PLAN GENERAL NOTES:

1. VERIFY ALL DIMENSIONS IN FIELD AND NOTIFY ARCHITECT OF ANY DISCREPANCIES.
2. VERIFY QUANTITY, SIZE AND LOCATION OF ALL FLOOR, ROOF AND WALL OPENINGS FOR MECHANICAL AND ELECTRICAL WORK WITH THE APPROPRIATE TRADES FOR ALL OPENINGS SHOWN ON RECORDS FOR THE COMPLETION OF THE WORK.
3. CONTRACTOR SHALL BE REQUIRED TO PROVIDE TEMPORARY CURTS AND FIRE-SHAED PARTITIONS TO SEPARATE AREAS DURING PAINTING AND PREP WORK.

TYPICAL CONSTRUCTION NOTES:

1. ALL WORK SHALL COMPLY WITH NATIONAL, STATE AND LOCAL CODES, ORDINANCES AND REGULATIONS.
2. ALL MATERIALS SHALL BE INSTALLED/APPLIED IN STRICT ACCORDANCE WITH MANUFACTURER'S REGULATIONS.
3. CONTRACTOR SHALL BE HELD RESPONSIBLE FOR VERIFYING THE JOB SITE AND FAMILIARIZING THEMSELVES WITH EXISTING CONDITIONS PRIOR TO START OF WORK. ALL DIMENSIONS AND RELATIONS SHALL BE VERIFIED AND BIDS FAILURE OF THE CONTRACTOR TO VERIFY ALL CONDITIONS PRIOR TO THE AWARD OF BID WILL NOT BE CONSIDERED AS GROUNDS FOR AN EXTRA.
4. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR MAINTAINING, MAINTAINING, AND SUPERVISING ALL SAFETY REGULATIONS AND PROGRAMS IN CONNECTION WITH THIS PROJECT. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR PROVIDING TEMPORARY PROTECTION TO INSURE THE SAFETY OF THE GENERAL PUBLIC DURING CONSTRUCTION.
5. ALL ITEMS SHALL BE AS SPECIFIED BY ARCHITECT.
6. SIGHT GAP BEHINDS PRODUCT DATA, AND SAMPLES TO THE ARCHITECT FOR REVIEW PRIOR TO INSTALLATION/APPLICATION.
7. ALL OTHERS SHALL BE LEGALLY DISPOSED OF OFF THE SITE BY THE CONTRACTOR.
8. ALL PRECAUTIONS SHALL BE TAKEN TO AVOID DAMAGE TO EXISTING MATERIALS AND CONSTRUCTION TO REMAIN.
9. CONTRACTOR SHALL KEEP NOISE, DUST, ETC., TO A MINIMUM STANDARD AS SET FORTH BY THE OWNER.
10. CONTRACTOR SHALL COORDINATE INSTALLATION AND PHASING OF WORK WITH THE ARCHITECT AND OWNER'S REPRESENTATIVE PRIOR TO THE START OF WORK.



COMPOSITE FLOOR PLAN
SCALE: 3/16"=1'-0"