



- Item A2** Drawing A3-01; PARTIAL FLOOR PLANS (revised but not re-issued)  
A. Floor slab infill at area removed existing floor slab for interior footing installation at DISHWASHING 102 to be included in base bid cost. Refer to key note 42 for similar notation.

**FOOD SERVICE DRAWINGS:**

- Item FSE1** Drawing FS-01 through FS-04; (revised but not re-issued)  
A. Disregard "NOT FOR CONSTRUCTION" notation.

**MECHANICAL DRAWINGS:**

- Item M1** Drawings M1-01A; LOWER LEVEL MECHANICAL PLAN – AREA A (revised but not re-issued)  
A. Condensate piping to be removed and replaced above ceiling area for reconnection to condensate piping riser in CASHIER 104.  
B. Provide new steam and condensate piping with associated control valve and condensate trap connected to existing steam at exterior wall, and existing condensate riser in CASHIER 104 for FCU1 and FCU 2.

**ELECTRICAL DRAWINGS:**

- Item E1** Drawings E600; ONE LINE DIAGRAMS (revised but not re-issued)  
A. Provide new RP-K3 panel with new conduit and feed wiring per the new one line diagram.

**\*\*END OF ADDENDUM\*\***