## ADDENDUM

Project Name:	Kosciuszko Middle School Toilet Room Upgrades	Addendum No:	Two (2)
Project Number:	16-118	Issue Date:	May 4, 2016
Project Location:	Hamtramck, Michigan		

To the Contract Documents for the requested Kosciuszko Middle School Toilet Room Upgrades

This Addendum forms a part of the above described Contract Documents and supersedes, supplements or clarifies parts thereof to the extent defined by the terms set forth in this Addendum.

This addendum consists of (2) typed pages and the following attachments:

### **SPECIFICATIONS**

# Item SP1Specification Section 000000 – PROJECT IDENTIFICATION (revised but not reissued)A. Bid due date to read:May 6, 2016, 2:00 p.m.

**Item SP1** Specification Section 024119 – SELECTIVE DEMOLITION (revised but not reissued)

- A. 1.5 FIELD CONDITIONS D. 1; materials found to be hazardous will be removed by the owner's Abatement Contractor.
- B. Reports indicate the tested materials in the basement areas including toilet rooms have been removed.
- C. Due to the age of the building the existing painted surfaces may contain lead containing pigments. The demolition of painted materials should proceed in compliance with standards indicated in paragraphs 2.1 A, B.

### STRUCTURAL DRAWINGS:

Item S1 Drawing S3-01; PARTIAL FOUNDATION PLANS (revised but not reissued) A. Section / detail sheet indications should reference sheet S3-01.

### MECHANICAL DRAWINGS:

- Item M1 Drawing MD1-01; Partial Underground Plumbing Plan (revised but not reissued) A. All under floor sanitary piping is to be removed in the existing toilet room areas.
- Item M2 Drawing P-100 First Floor Plumbing Plan (revised and reissued this Addendum)
  - A. The existing below floor sanitary sewer line in corridor is approximately centered in the corridor and 12 feet below the floor elevation.